BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Supply and Errection of compact Floating Foaming Jet Aeration of 6 mtrs height with RGB LED light including HI installation in Yelahanka old town Tank Ward no.01

Agency:-Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)

NEGOTIATED SCHEDULE-B

Sl No	*App Qty*	*Description of work*	Unit	Negotiated Rates quoted by Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)	
				In Figure	*In Words*
1	3.00	Supplay, Instalation Testing And Commissioning of of COMPACT floating foaming Jet Aerator. The Aerator is mounted on an unobtrusive circular float built in international standards in GRP With alluminium sub frame for complete corrosion rasistance there are four separate compartments each fitted with closed cell foam prevents the entry of water even if floot holed with 3HP Motor 4 Nos RGB(0.084KW) lights completly integrated Package, factory assembled so as to achive the best possiable display and precision of the Water Jets and effects. The pump set is exactly matched to the fountain,The work should be carried out as per the directions of the incharge Engineer including lead & lift	Set	452500.00	Rupees Four Lakh(s) Fifty Two Thousand Five Hundred Only
2	200.00	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanished, steel wire/steel tap armoured cable with PVC outer sheating 1.1 KV class.I. Class 'A' PVC Cable. 3.5 core 25 sqmm	Mtrs	165.60	Rupees One Hundred Sixty Five And Paise Sixty Only
3	200.00	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct. 25 sqmm to 75 sqmm	Mtrs	16.00	Rupees Sixteen Only
4	50000.00	Fabricating supplying and mounting MS box made out... SWG suitable Ifor floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size cdlamps with mecessary cable entry pipe with gland and box should be finished with 2 cdoats of red oxide primer paint and finally finished with approved colour enameled metal pain etc., complete. b)16 swg	Sqcm	0.33	Rupees And Paise Thirty Three Only
5	10.00	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a)40X40X6mm	Mtrs	263.00	Rupees Two Hundred Sixty Three Only
6	3.00	Supplying and fixing miniature circuit breakes on exisiting MCB distribution boards using necessary fixing materials and wiring complete as required. b) 40-63Amps DP,2. Group 'A'	Nos	1093.00	Rupees One Thousand Ninety Three Only
7	3.00	f)40-63Amps TPN, Group A	Nos	1936.00	Rupees One Thousand Nine Hundred Thirty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
31/7/18

	Approx Qty	Description of work	Unit	Negotiated Rates quoted by Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)	
				In Figure	*In Words*
8	200.00	Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to table 3 class 5 of IS:8130-1984 and (Virgin) PVC insulation and sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A.4C X 2.5Sq.mm	Mtrs	105.90	Rupees One Hundred Five And Paise Ninety Only
9	300.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A 3C X 6.0Sq.mm(150Mtrs x 2 Runs)	Mtrs	188.70	Rupees One Hundred Eighty Eight And Paise Seventy Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division
Yelahanka Zone